


History of original corner establishment:

A 30"x18"x3" Basalt Stone with 4 notches on South side and 3 notches on East side.

24" Fir N15E 144 lks. T1S S10 BT  
 18" Fir N30W 222 lks. R37E S9 BT  
 12" Fir S18W 252 lks. S16 BT  
 10" Fir S82E 223 lks. S15 BT



J-13

Description of corner evidence found:

Found original stone in mound of stone.


24" Fir snag S82E 147.2' (Scribes visible)

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2"x30" Iron pipe with brass-cap.  
 Pipe is set in mound of stones with original stone near bottom.  
 Brass-cap marked: T1S R37E  
                           S9 S10  
                           S16 S15  
                           1978  
                           RLS 346

40" Fir S30E 265.2' Mkd. T1S R37E S15 BT  
 14" Fir N32E 192.8' Mkd. T1S R37E S10 BT  
 10" Larch N18W 144.5' Mkd. T1S R37E S16 BT  
 8" Fir S35W 151.4' Mkd. T1S R37E S16 BT

All BT's have BT signs and red painted stripe. The new BT's have a brass washer stamped RLS 346 nailed to the lower face. There is a 6' steel fence-post within 5' of the corner.



Office of... COUNTY SURVEYOR..... County of... UMATILLA.....  
 State of... OREGON....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)