

Index
File No. J-07


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____
Cor. No. _____

T 1S R.37E R.D. WALLA WALLA County UMATILLA
Merid. WILLAMETTE N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found no evidence of the original corner monument.

NOTE: A mound of stone was found S17°E, 36 feet from the found original Northwest bearing tree described below.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found a stump hole S52°W, 189 lks with rotted remains of Fir with no marks visible.
Found a 28 inch diameter Douglas Fir N29°W, 159 lks live and vigorous with blaze evident. The tree had been opened on at least 2 previous occasions. Due to the discrepancy between the bearing tree and the mound of stone, I opened the tree, finding the ¼S scribes.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on open South slope approximately 300 feet South of the end of the 023 road.

PHOTO IDENTIFICATION DATA

12 616140A 787-151

Photo No. _____

Filed At. Ranger Office

Object Iden Bearing Trees

Ident. By D.I. Griffith

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Title
Surveyor

Division

Headquarters

Date

FS-7100-52 (3/68)

8-24-89

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½"x30" aluminum pipe with aluminum cap marked as shown:
 Pipe is set 10 inches in the ground.

T1S R37E
 S 8
 ¼
 S 17
 1989
 OPLS 644

Raised a mound of stone around monument, 4 ft. base to top of cap.

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BTs:

A 13 inch diameter Ponderosa Pine bears N23°E, 58.62 feet marked ¼ S8 BT
 A 15 inch diameter Ponderosa Pine bears S35°E, 105.80 feet marked ¼ S17 BT

Painted a 6 inch red band around all bearing trees and attached 54-3 and 54-9 signs.

Set a steel fence post approximately 5 feet North with 54-9 sign attached.

Work Done By D.I. Griffith Title Surveyor Date 8-18-89 State Registration No. OPLS 644
 or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla Co. Surveyor's Office Date 9-89

REMARKS

Witness: Jeff Petersen

Index File No. J-07 T. 1S R. 37E W.M. Tract or Surv. No. Cor.

LAND CORNER RECORD

LL 5680-2

(Rectangular)

1. T 1S R 37E No. J-7 Cor. 1/1 Mer. Will State Oregon N. F. Matilla Dist. Pendleton

2. Corner Status

3. Original Description _____ Vol. _____ Page _____ Where Recorded _____

4. Description of Corners: No description.

7. Photo Identification

Photo No. _____

Ident. By: _____

5. Investigation Notes:

Found 24" x 12" x 10" stone. No marking on stone 24" D. Fir has 21" high, 10" wide and 4" deep blaze appears to be very old but the inside of it has been chopped out in recent years. I could not find any markings in blaze at a bearing of S 17° E and 36 Ft. away. No other bearing trees could be found.

8. Plane Coordinate Position Data

State _____ Zone _____

X _____

Y _____

Estab. By _____

Field Book No. _____

Where Filed _____

9. Evaluation

Authentic _____

Needs Verif. _____ Monument NO

Re-estab. ~~3~~ Survey X

Land Status _____

6. Signed N. Carr Title Eng. Aid Date 7-6-65

PERPETUATION RECORD

10. Monument:

11. Accessories

Field Book _____ Page _____

12. Set By _____ Title _____
License _____ Agency _____ Date _____

13. Recorded By: _____ Volume _____ Page _____
(Agency)

(Date) (City) (County) (State)

14. Remarks:

J-7