


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:

Set post 4 ft long 4 in square 24 in in ground for cor to secs 17, 18, 19 + 20 marked T1S S17 on NE, R37E S18 on NW, S19 on SW and S20 on SE with 3 notches on S and 5 on E edges, from which;

- A fir 5 in diam bears N47°E 39 lks dist marked T1S S17 BT
- A fir 12 in diam bears S70°E 41 lks dist marked S20 BT
- A pine 36 in diam bears S20°W 29 lks dist marked S19 BT
- A fir 10 in diam bears N50°W 77 lks dist marked R37E S18 BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument.

- Found a stump hole N47°E, 39 lks.
- Found a 15 inch diameter Fir snag S70°E, 41 lks, dead 10 ft. high snag with BT scribe visible.
- Found a 36 inch diameter Ponderosa Pine S20°W, 29 lks, dead and down on face.
- Found a stump hole N50°W, 77 lks.

Description of monument and accessories I established to perpetuate the

original location of this corner: At record bearing and distance from the above described found bearing trees, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which:

- New BTs:
- A 9 inch diameter Douglas Fir bears N8°E, 28.64 feet marked T1S R37E S17 BT on single blaze
 - A 12 inch diameter Douglas Fir bears S27°E, 55.50 feet marked T1S R37E S20 BT
 - A 14 inch diameter Douglas Fir bears S50°W, 46.8 feet marked T1S R37E S19 BT
 - A 8 inch diameter Douglas Fir bears N60°W, 22.0 feet marked X BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.
Set a steel fencepost approximately 5 feet North with land survey monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 27, 1989.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept. County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 27th day of October, 1989
David H. Chamberlain by Kathleen K. Ambery
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

*GPO-591-971, 1988

RECEIVED BY
 Date 10-19-89
 Initials A
 No. 89-106-R