


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Set a 14"x8"x6" Basalt Stone 9" in the ground.
8" Fir N47W 24lks. Mkd. R37E S17 BT
24" Pine N43E 14 lks. Mkd. T1S S16 BT
30" Pine S67E 42 lks. S21 BT
9" Fir S15W 72 lks. Mkd. S20 BT



14-9

Description of corner evidence found:

Mound of stones with old red flagging.
Fir snag S20W 40.0' (Scribing not visible)

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2"x30" Iron pipe with brass-cap marked: T1S R37E
S17 S16
S20 S21
1978
RLS 346
8" Fir S19E 78.9' Mkd. T1S R37E S21 BT
8" Fir N35E 67.6' Mkd. T1S R37E S16 BT
8" Pine N54W 119.4' Mkd. T1S R37E S17 BT
6" Pine S38W 150.1' Mkd. T1S R37E S20 BT

All BT's have a red painted stripe and BT signs. The new trees have a brass washer stamped RLS 346 nailed to the lower face. There are 2-6' steel fence-posts set on line apx. 5' from corner.



Office of...COUNTY SURVEYOR..... County of... UNION
State of... OREGON I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)