


History of original corner establishment:



A WOODEN POST 3'x 3 SQ. IN. 24" IN THE GROUND

15" PINE S38W 27Lks. MKD. 1/4 S BT

15" PINE S57E 17Lks. MKD. 1/4 S BT

Description of corner evidence found:

15" ROTTEN PINE STUMP S38W 17.8'

15" ROTTEN PINE STUMP S57E 11.2'

SCRIBING NOT VISIBLE. THESE TREES MATCH THE DESCRIPTION OF THE US FOREST SERVICE NOTES.


THERE IS A STONE SET BY RLS 645 APX. S68E 6.2' FROM THE CORNER

Description of monument and accessories established to perpetuate the original location of this corner:

SET 2"x30" IRON PIPE WITH A BRASS-CAP MARKED: TIS R37E
 S30 1/4 S29
 1978
 RLS 346

14" FIR S67W 33.3' MKD. 1/4 S30 BT
 8" FIR N74E 12.0' MKD. 1/4 S29 BT

THE BT'S HAVE BT SIGNS AND A RED PAINTED STRIPE. THE TWO NEW TREES HAVE A BRASS WASHER STAMPED RLS 346 NAILED TO THE LOWER BLAZE. THERE IS A 6' STEEL FENCE POST WITHIN 5' OF THE CORNER.



Office of COUNTY SURVEYOR County of UNION
 State of OREGON, I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)