

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/21/17.

CORNER DESIGNATION: E-1, The Southwest corner of Section 6, Township 2 North, Range 28 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by David P. Thompson Contract No. 83 dated July 22, 1859. Notes state: Set post corner for corner to Secs. 6, 7, 1 and 12 in mound of earth & as per instructions. The corner may have been computed by John Kimbrell, Deputy County Surveyor, in Survey No. 357, recorded at Record of Private Survey Book 2, Page 216, in December, 1912. Kimbrell's notes do not indicate anything set. Criger Survey No. 07-92-B, in October 1935, indicates a buried stone was set or found at the corner point. The position for this corner point was computed by Steve Haddock in his Survey No. 13-555-C in 2013, after evaluating old fence intersection evidence reported in Krumbein Survey No. L-42 A.

MONUMENT AND ACCESSORIES FOUND: None. I probed for the 1935 record stone but did not recover it. It is suspected the County Road has shifted over the years and displaced the stone. I reestablished the corner point at the position reported on Survey No. 13-555-C.

MONUMENT MARKING DETAIL:

T2N  
R27E R28E  
S1 | S6  
-----  
S12 | S7  
2017  
PLS 1106

MONUMENT SET: At the reestablished corner point, set a 1 1/4" by 30" galv. iron pipe with 2 3/8" brass cap 30" in the ground. Cap is marked as shown in "Monument Marking Detail". Placed a large granite stone and smaller basalt stone in a mound beside corner monument.

New accessories:

- A 5/8" by 30" rebar with 1 1/4" red plastic cap bears N 47° E, 26.7 feet.
- A 3/4" brass washer stamped "PLS 1106" nailed to UECA power pole No. 70900, 3 feet above ground line bears S 45° E, 34.6 feet.
- A 5/8" by 30" rebar with 1 1/4" red plastic cap bears S 53° W, 13.8 feet.
- A 5/8" by 30" rebar with 1 1/4" red plastic cap bears N 29° W, 18.6 feet.

Red plastic caps are marked "ORPLS 1106 WAPLS 17372". Nailed "bearing object" sign to the power pole by the brass washer and wired "bearing object" signs to the rebar accessories. Set steel fence post 2 feet South of corner with "witness" sign wired to it.

LOCATION AND COMMENTS: Corner falls at the North end of an old fence line extending South and approximately 30 feet South of Eagle Ranch Road.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

\2N28E1



renews 6-30-18

17-065-C