

**OREGON CORNER RESTORATION FORM**

SECTION: 12 TOWNSHIP: 2N RANGE: 29E J-25

COUNTY: UMATILLA DATE: 8/2010

**CORNER DESIGNATION**

SE 12

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Thompson under Contract #83 in 1859. He set post and made mound.

**MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE**

Nothing Found

**MONUMENT DETAIL**

T2N  
 R29E R30E  
 12| 7  
 13| 18  
 2007  
 LS 951

**OREGON STATE PLANE COORDINATES NORTH ZONE, NAD 83(91), Int Feet:**

730092.73  
 8554424.30

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

In a cultivated field by single proportion I set a 2 3/8" brass cap on a 1" x 12" iron pipe 20" below the surface.

**NEW ACCESSORIES FROM WHICH**

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 34° 57' 07" E 881.32'  
 A 10" bridge spike and a blue mag. 24" deep bears S 72° 35' 54" E 31.57'  
 A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 37° 29' 08" W 544.62'  
 A 5/8" x 30" Iron Rebar with plastic cap \*951 bears N 88° 44' 15" W 542.54'  
 These bearings and distances are State Plane.


**LOCATION AND COMMENTS**

From Cunningham sheep ranch shop go westerly on Cunningham Road 1.1 mile to BPA power line crossing. Go South up a draw and into fields 1.6 mile to corner.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC  
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: G. EDWARDS  
 WITNESS: R. SMITH



11-68c