

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 17
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on August 30, 1859, under GLO contract No. 83, as follows:

Set a post for section corner with mound of earth & etc., per instructions.

T2N R30E
S10|S11
S15|S14
PLS 1636
2003

On November 18, 1904, County Surveyor John W. Kimbrell perpetuated this corner position as follows: Beginning at the corner to sections 10, 11, 14 and 15. Set a stone with mound and pits.

On June 15, 1999, Gary B. Wagner, PLS 2817, found and accepted a mound of basalt stones with a railroad tie lying alongside. His map indicates a tie to this corner is shown on the right-of-way map for the Bonneville Power Administration electrical transmission line. See County Survey Map No. 99 - 133 - B.

Original corner evidence recovered:

Found a mound of stones. None of the stones have visible marks. In the center of the mound I find a 1 1/2" x 1 1/2" x 10" wood hub with a hub tack in the top and a red plastic rebar cap lying loose alongside the hub, with marks "R.S.I. CONTROL" on the top of the cap.

Monument and accessories established to perpetuate the original position of this corner:

In place of the wood hub, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the hub and red plastic cap at the base of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 11", attached at ground level, bears N37° E, 134.2 feet.

The northerly wooden power pole for BPA transmission line, with identifying marks "BONNEVILLE POWER ADM MCN RND 26 1 A", bears S54° E, 84.4 feet. I nail a 3/4" brass washer, marked "PLS 1636 14", to this pole one foot above the ground, and a "Bearing Object" sign 5 feet above the ground.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 15", attached at ground level, bears S51° W, 183.3 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 10", attached at ground level, bears N14° W, 139.1 feet.

I hereby certify the above corner point was perpetuated as hereon described on November 4, 2003. Magnetic declination set in compass: 16° E.
NAD '83 UTM Zone 11 position: 5058439N, 341269E (plus or minus two meters).

RECEIVED BY
Umatilla County Surveyor
Date 2-04
Rec'd By KK
No. 04-32-R

Renews June 30, 2005

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: