

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/23/06

CORNER DESIGNATION: 2N31, N-1, The Southwest Corner of Section 18

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for corner to Secs. 18, 19, 13 & 24 and build mound of earth with pits, trench &c., as per instructions. BPA Pendleton-McNary Transmission Line Survey, maps dated 1950, show a stone found, with State Plane coordinate value. BPA maps found in County Assessors Office.

MONUMENT AND ACCESSORIES FOUND:
Found 18"x9"x4" stone set firmly in ground with top 3" above ground level in small mound of stone. There is also a 2 foot long, by 3" diameter, burnt piece of larch post near the mound.

MONUMENT MARKING DETAIL:

T2N
R30E R31E
S13|S18
S24|S19
2006
PLS 1106

MONUMENT SET:

At the position of the found set stone, set a 1 1/4" x 30" galvanized iron pipe with 2 3/8" brass cap, 26" in the ground. Raised mound of earth and stone to top of cap. Placed corner stone in mound of earth and stone 1 foot South of new monument. Stamped cap as shown in Monument Marking Detail.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North, 30.1 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 43° East, 34.9 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 12° West, 38.0 feet.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 75° West, 37.7 feet.

Attached bearing object signs to all rebar accessories. Set steel fence post with witness sign 2 feet East of monument.

LOCATION AND COMMENTS:

Corner is located in a steep unfarmed draw sloping East approximately 30 feet West of the bottom of the draw.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 725535.57
E = 8586479.47

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/2N31N1

Surveyor's Seal



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

1106-4102-C