

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N , R 32E. , W.M.

Corner Code No. E-5

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by D. Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated August 21, 1884. The original notes state that at the corner a wood post, with charred stake, earth mound and pits, was established for the corner.

In 1961, Map No. Q-1047-C shows that a 5/8" iron rod was established for the corner by Stanley G. Wallulis.

City Map No. 11-7711, originally prepared and dated 12-18-74, shows a stone found for the corner.

Corner card at the City of Pendleton states "Found stone with chiseled "X" approximately 6" below ground surface, 7.2' S.W. of highway right-of-way fence and 8.4' N.E. of right-of-way station 1237+30". No date is indicated.

This corner was re-monumented by Dave Krumbain in 1985.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found 2 1/2" brass cap on 1 1/2" galv. iron pipe, in good condition, projecting 4" from the ground.

Note: A search was made for the 5/8" iron rod shown on map Q-1047-C, without success.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained the monument by surrounding with a mound of earth. Referenced the existing monument as follows:

An existing 1 1/2" alum. cap on 5/8" iron rod, marked "Oregon State Highway Dept.", bears S78°W 8.52'.

The N.W. corner of a 2 1/2" by 2 1/2" angle iron fence corner, set in concrete, bears N58°E 7.16'. (Measure to the N.W. cor. of angle iron at concrete level).

A aluminum nail in the east side of a cut off telephone pole 15' high bears S1°W 5.74'.

Set steel fence post east of corner monument and attached witness corner sign.

Attached bearing object sign to the angle iron fence post set in concrete.

Attached witness corner sign and bearing object sign to the 15' high telephone pole that the aluminum nail is in.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)