

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/13/06

CORNER DESIGNATION: 2N31, G-25, The East One-Quarter Corner of Section 12.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

In Survey No. 88-19-C, I had previously searched this corner area and determined the corner was farmed out. I had established the South 1/16th corner between Sections 12 & 7 in Survey No. 88-19-C.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N
R31E R32E
1/4
S12 | S7
2006
PLS 1106

MONUMENT SET:

Re-established corner, by single proportion measure, between the recovered Northeast corner of Section 12 and the recovered South 1/16th corner on the East line of Section 12. See Survey No. 88-19-C. At reestablished corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe, 27" in the ground to bedrock. Monument marked as shown in monument marking detail. From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 38 1/2° East, 34.4 feet
 - A blue Deep-1 magnet buried 22" below ground level bears South 25° East, 24.6 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 65 1/2° West, 36.6 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 26 1/2° West, 39.5 feet.
- Buried bearing object signs with all magnets. Set steel fence post with witness post sign 1 foot North of monument.

LOCATION AND COMMENTS: Corner is located on a ridge top in a CRP field. No other features nearby.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 733565.98
E = 8618422.18

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/2N31G25

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-c