

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. L-17


Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

"Set a basalt stone 8x8x8 ins, 6 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on W. face dug pits 18x18x12 ins N & S of Cor. 5 1/2 ft dist. Raised earth mound 1 1/2 ft high 3 1/2 ft base alongside."

In January 1956, Charles Eddleman, surveyor for the city of Pendleton, reported a 1" iron pipe set for the corner. (City Map Record 24-7509).



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" iron pipe buried 1.7' below surface. This monument was verified by survey to section corners to the North and South. The found monument is believed to be a perpetuation of the iron pipe set by Eddleman in 1956.

Description of monument and accessories | established to perpetuate the original location of this corner:

Remonumented with a 2 1/2" brass cap on a 1" by 30" galv. iron pipe buried 12" below ground with found iron pipe buried horizontally on West side of new monument. From the remonumented corner point:

- A 5/8" by 30" iron pin bears N 9 1/2°W - 97.26'. Pin at base of fence corner with a Bearing Object sign nailed to railroad tie corner post.
- A 5/8" by 30" iron pin bears N 61°E - 89.05', with a steel fence post set approx. 1' from pin with a Bearing Object sign attached.
- A 5/8" by 30" iron pin bears S 15°E - 233.92'. Pin at base of chain link fence post with a Bearing Object sign attached to post.
- A 5/8" by 30" iron pin bears S 26 1/2°W - 205.45'. Pin is at base of chain link fence post with a Bearing Object sign attached to post.

All iron pins capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

Set a steel fence post 4.0' North of monument and attached a Witness Corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by (DEPUTY)
(COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor
Date 8-92
Rec'd By RR
No. 92-92-C