

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E . , W.M.

Corner Code No. N-19


Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

Set a basalt stone 18x16x6 ins. 12 ins. in the ground for 1/4 sec. cor. mkd. 1/4 on W. face. Dig pits 18x12 ins. E & W from stone 5 1/2 ft. dist. Raised earth and 1 1/2 ft high 3 1/2 ft base alongside.

Survey No. R-77-A calls for a found pipe at the corner position.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

A 2" by 44" iron pipe with a 18" by 12" by 6" stone marked "1/4" buried alongside. There is a North-South fence 1.9 feet East of monument.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe 22" in ground and buried old pipe horizontally at the base. Surrounded monument with a mound of stone and placed found 1/4 scribed stone in base of mound. From the new monument:

- A 5/8" by 30" iron pin bears N 04°E - 25.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.
A 5/8" by 30" iron pin bears N 55°E - 20.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.
A 5/8" by 30" iron pin bears S 00°W - 20.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.
A 5/8" by 30" iron pin bears S 84°1/2 W - 25.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.

Set a 5.5 foot steel fence post, on rough line, approximately 1 foot from each pin, with a Bearing Object information sign attached.

Set a steel fence post 3' North of monument and attached a Witness Corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR
W.R. Wells
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....
..... by (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By KR

No. 92-92-C