

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. N-23

Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record by Currin and Noland, under Special Contract dated May 4, 1887 states:

Set a stone 12 X 9 X 7 ins. 8 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on N. face. Dug pits 18 X 18 X 12 ins. E & W from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 5 1/2 ft. base over it.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

The corner area has been extensively farmed over the years. Ther is an old North-South fence through the corner area with cultivated fields on both sides of the fence. I re-establish this corner at the intersection of the North-South fence and a line between the re-established S.E. corner of Section 13 and the proportioned latitudinal position for the S.W. corner of Section 13.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe 26" in ground and surrounded with a mound of earth, from which:

- A 5/8" x 30" iron pin bears N 0 1/2° W, 41.4'.
- A 5/8" x 30" iron pin bears N 0 1/2° W, 14.0'.
- A 5/8" x 30" iron pin bears S 0 1/2° E, 64.0'.
- A 5/8" x 30" iron pin bears S 0 1/2° E, 27.3'.

Each pin is capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

Nailed Bearing Object signs to wood fence posts by each reference pin.

Set a steel fence post 3.0' North of monument and attached a Witness Corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)
(COUNTY OFFICIAL)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 8-92

Rec'd By KK

No. 92-92-C