

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., .M.


Corner Code No. N-3

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Daniel Chaplin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1884. The original notes state:

Set post for 1/4 Sec. Corner in mound of earth charred stake and pits as per instructions.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

No evidence was found at the corner point. There is a field line and old North South fenceline running through the corner area. After confirming the location of the fenceline by survey, I re-establish the corner point at the intersection of the North South fence line and a line between the re-established positions of the Northwest and Northeast Corners of Section 19.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner position determined by survey, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 22" in the ground and surrounded with a mound of earth and stone.

The corner monument is referenced as follows:

A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106" bears S 02°E 30.4'. Placed bearing object sign on steel fence post by reference monument.

A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106" bears N 02°W 40.7'. Placed bearing object sign on wood fence post near the reference monument.

A brass washer stamped "PLS 1106", nailed to the South side of a 8" by 8" railroad tie fence post bears N 40°W 85.2'. The washer is about 1' above ground. Placed bearing object sign on the railroad tie fence post.

A steel fence post bears North 2.1' from the corner monument with witness corner sign attached.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-9-77

Rec'd By KK

No. 92-97-P