

ARTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E. , .M.

Corner Code No. N-5

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by Daniel Chaolin, U.S. Deputy Surveyor, under Contract No. 107, dated September 21, 1864. The original notes state:

Set post for corner to secs. 17, 18, 19 & 20 in mound of earth with charred stake, pits and etc. as per instructions.

The 1950 Bonneville Power Administration power transmission line maps show a tie to a 4 way fence corner existing at the time. This fence corner was called the Section corner on the BPA maps.

In 1980, during Survey No. R-28-B, the corner position was computed based on the BPA ties, and shown on a Section breakdown diagram.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

The corner point now falls in an active wheat field, - no trace of the fences existing in 1950 remain. This corner position was re-established based on ties to Survey No. R-28-B, measuring the record distance reported on Survey R-28-B, from the brass capped iron pipe monument at the Southwest corner of Section 20. The 5/8" iron pin at the intersection of the South righth-of-way line of the BPA transmission line and the Section line common to Sections 19 & 20 was used to determine alignment of the Section line. (See Map No. R-28-B).

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, with the top of the brass cap buried 18" below the ground.

No accessories were placed for this corner. It is in an area which is farmed in all directions for some distance.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By RR

No. 92-92-C

☆ GPO-788-276