

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. R-23


Note: Monument marked as shown below

History of original corner establishment:

The corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864, set post and charred stake in mound of earth, pits and etc., as per instructions.

This corner was reset by Z.F. Moody, under Contract No. 165, dated October 4, 1871. Moody set a post and made an earth mound for the corner.

The corner was recovered and re-monumented by Currin and Noland, under Special Contract dated May 4, 1887. Currin and Noland found the "Old Corner", and re-monumented with a 9 x 8 x 7 inch stone set 6 inches in the ground with pits dug East and West of corner and a mound of earth raised alongside the corner.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

No evidence found. Corner was re-established by single proportion measurement between the Southwest and Southeast corners of Section 24.

This corner falls in an active farmed field.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 45 inches in the ground, in the middle of a wheat field.

New Bearing Objects:

- A 5/8" x 30" iron pin bears N 66° E - 22.9 feet. (Buried 22" below ground).
- A 5/8" x 30" iron pin bears S 32° E - 20.1 feet. (Buried 16" below ground).
- A 5/8" x 30" iron pin bears S 66° W - 21.5 feet. (Buried 15" below ground).
- A 5/8" x 30" iron pin bears N 34° W - 20.7 feet. (Buried 16" below ground).

All iron pins are capped with a 1 1/2" yellow plastic cap marked: "WR WELLS, PLS 1106". Bearing Object signs are wired to each iron pin.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12/31/94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)