

Note: Monument marked as shown below


**History of original corner establishment:**

The corner was originally established by David Thompson under Contract No. 106, dated August 16, 1864. Thompson set a 20 x 12 x 4 inch stone for the corner.

The corner was recovered by Z.F. Moody, under Contract No. 145, dated April 23, 1871.

The corner was recovered by Currin and Noland, under Special Contract dated May 4, 1887. Currin and Noland found the old pits and mound for the corner and re-monumented with a 18 x 6 x 6 inch stone set 12 inches in the ground, with pits redug and a mound of earth built alongside.

The corner was re-established by L.E. Wilkes, G.D. Surveyor, in 1917. Wilkes set a iron post, 3 feet long, 2 inches in diameter, 24 inches in the ground for a witness corner to the true corner point. This witness corner is located 45 1/2 lks West of the true corner point.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

No evidence found. The corner area has been worked extensively during culvert installation and ditching. The corner was re-established by single proportion measurement between the Northwest corner of Section 30, T2N., R33E., and the North 16th corner of Section 30, T2N., R33E., W.M.. The 1988-1989 BLM survey of Section 30, T2N., R33E., W.M., was used for the proportioning record.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 44 inches in the ground. Monument is 2.5 feet East of the West edge of a gravel road.

Set a steel fence post 5.0 feet West of the monument, with a Witness corner sign attached.

**New Bearing Objects:**

- A 5/8" x 30" iron pin bears S 15° W - 51.8 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears S 44° W - 11.2 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears N 63° W - 7.3 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears N 55° W - 34.8 feet. (Flush with the ground).

All iron pins are capped with 1 1/2" yellow plastic caps, marked "WR WELLS, PLS 1106". Bearing Object signs are wired to each iron pin.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*expires 12/31/94*

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)