

OREGON CORNER RESTORATION FORM


COUNTY: Umatilla DATE: 4/14/94

CORNER DESIGNATION: T-25. East 1/4 of Section 25. T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by L.E. Wilkes, GLO Cadastral Surveyor, in 1917. L.E. Wilkes set an iron post 3 ft. long, 2 ins. diam., with brass cap, 24 ins. in the ground for a witness corner to the East 1/4 of Section 25 only. Wilkes witness corner monument was set 45 1/2 Lks West of true corner point. A 1988-1989 survey by Richard L. Johnson, Cadastral Surveyor for BLM, showed the Wilkes witness corner to be in a disturbed position, and the position of Wilkes witness corner was not accepted by BLM.

MONUMENT AND ACCESSORIES FOUND: Found Wilkes witness corner monument, a 2 1/2" brass cap on 2" galvanized iron pipe at East end of a fenceline extending West. This monument was rejected because of its disturbed location. Disturbed Wilkes' witness corner bears N 15°58' W-19.4 feet from true position of the East 1/4 corner of Section 25.

MONUMENT MARKING DETAIL:



MONUMENT SET: Re-established corner position by single proportion measurement between the West 1/4 corner of Section 30 and the South 1/16th corner of Section 30, and set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 39" in the ground.

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 3 1/2° W-26.5 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 6° W-15.4 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 48 1/2° W-24.5 feet.
Power pole No. 259560 with a brass washer stamped "PLS 1106", attached 5" above ground, bears N 7 1/2° W-19.7 feet.
Attached bearing object tags to iron pins. Set steel fence posts near iron pins with witness signs attached. Power pole has witness sign attached.

LOCATION & COMMENTS: Corner is located in a field access road area. Top of monument is 9" below ground.

COMPASS DECLINATION: 18° East.
FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

