

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 4/14/94

CORNER DESIGNATION: V-19. North 1/4 corner Section 35, T2N., R32E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Set stone 8 x 10 x 12 ins., 8 inches in the ground for 1/4 Sec. corner, marked 1/4 on N. face. Dug pits 18 x 18 x 12 ins. E & W. from stone 5 1/2 ft. distant and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it. This corner was re-established by PLS 1280 in 1982 in Umatilla County Survey No. 82-51-C.

MONUMENT AND ACCESSORIES FOUND: Found 3" brass cap on galvanized iron pipe set 12" below ground per Umatilla County Survey No. 82-51-C. This corner monument was rejected because it was established using the Daniel Chaplin rather than Currin and Noland GLO record.

**MONUMENT MARKING DETAIL:**

T2N R32E  
S26  
1/4 ———  
S35  
1994  
PLS 1106

MONUMENT SET: Corner position was re-established by single proportion measurement using the GLO record by Currin and Noland, between the Northwest and Northeast corners of Section 35. At re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 44" in the ground, (marked as shown in the monument detail). The rejected monument by PLS 1280 bears S 58° 37' E, 2.6 feet.

**New Accessories:**

Power pole No. 264002 with a brass washer stamped "PLS 1106", nailed 1 foot above ground, bears N 2° E-109.3 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 38° E-21.7 feet, top set 1.3 feet below ground.  
An 11" diameter fence corner post with a brass washer stamped "PLS 1106", nailed 0.7 feet above ground, bears S 85° W-32.9 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 51° W-39.7 feet.  
Attached bearing object signs to iron pins, power pole, and fence corner post. Attached witness signs to power pole, fence corner post, and steel fence posts.

LOCATION & COMMENTS: Corner falls in a pasture.

COMPASS DECLINATION: 18° East.  
FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

Surveyor's Seal

