

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 4/22/94

CORNER DESIGNATION: X-13. East 1/4 corner Section 33, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. They found Old 1/4 Sec. cor. reset stone 10 X 8 X 8 ins., 7 ins. in the ground for 1/4 Sec. corner, marked 1/4 on W. face, redug pits 18 X 18 X 12 ins. N. and S. from stone 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N    R32E  
      1/4  
S33    |    S34  
      |  
      1994  
      PLS 1106

MONUMENT SET: Re-established corner by single proportion measurement between the Northeast and Southeast corners of Section 33. At the re-established corner position, set a 2 1/2" brass cap on a 1 1/4" X 30" galvanized iron pipe, 26" in the ground, with a mound of stone to the cap, (marked as shown in the monument detail).

New Accessories:

Set steel post with witness sign attached 1.4 feet North of monument in fence.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 41° E-16.4 feet, top set 1.5 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 36° E-17.6 feet, top set 1.2 feet below ground.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 9 1/2° W- 14.7 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLA 17372" bears N 5 1/2° W- 14.8 feet.

Attached bearing object sign to iron pin, set steel fence post nearby with witness corner sign attached.

LOCATION & COMMENTS: Corner falls in a North-South fenceline on ridge East of Old Highway 395.

COMPASS DECLINATION: 18° East  
FIRM/AGENCY: William R. Wells, PLS  
                  P.O. Box 1696  
                  Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106