

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/18/94

CORNER DESIGNATION: Z-11. South 1/4 corner Section 33, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC: Most recent approved GLO survey was made by David P. Thompson, under Contract No. 106, dated August 16, 1864. Original notes state: set post for 1/4 sec. corner from which: A balm, 5 ins. diam., bears S 17° E. 79 lks. dist.. A balm, 15 ins. diam., bears N. 87° W. 100 lks. dist..

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T32E T2N
S33
1/4 ---->----
S4
1994
PLS 1106

MONUMENT SET: Re-established corner position by single proportion measurement between the Southwest corner and Southeast corner of Section 33. Set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 25" in the ground, with a mound of stone to cap. (marked as shown in the monument detail)

New Accessories:

Set steel fence post with witness sign attached 1.6 feet North of monument.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 55° E-22.0 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 50° E-23.7 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 27° W-16.2 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLA 17372" bears N 45 1/2° W-16.8 feet.
Attached bearing object signs to iron pins. Set steel fence posts near iron pins with witness signs attached.

LOCATION AND COMMENTS: Corner falls 16 feet East of Birch Creek.

COMPASS DECLINATION: 18° East

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

EXPIRES
JULY 22, 1997
WILLIAM R. WELLS
1106

renews 12-31-94