

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 33E., W.M.


Corner Code No. C-1

Note: Monument marked as shown below

History of original corner establishment:

The N.W. Corner of the Diminished Umatilla Indian Reservation was originally established by Currin and Noland et al. under Special Instructions and Contract dated May 4, 1887. The original notes state that at the corner a 16" square by 36" long basalt stone was set for the corner marked "N W COR RES D R".


This corner was recovered by L.E. Wilkes, during his resurvey of part of the diminished boundary of the Umatilla Indian Reservation in 1917. Wilkes record states "The N W Corner of the Diminished Umatilla Indian Reservation, which is a basalt stone, 12 by 10 ins. 2 ins. below the surface of the ground, marked as described by surveyor general. At a point 1 1/2 S. of cor. I set an iron post, 3 ft. long, 2 ins. diam., 28 ins. in the ground, for witness cor. to the N.W. cor. of Diminished Umatilla Indian Reservation, with marked brass cap".



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

A 12" by 10" top dimension basalt stone, marked "N W COR RES" on east face. This is the stone established by Currin and Noland under Special Instructions and Contract dated May 4, 1887. Also found a 2 1/2" brass cap on 2" by 36" iron pipe set 1 1/2 south of the corner stone. The brass capped iron pipe is badly bent. The brass capped iron pipe monument is the one established as a witness corner by L.E. Wilkes in 1917, and is marked:



Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the witness corner monument set by Wilkes in 1917, which is S0°11'30"W 0.66' from the corner stone monumenting the N.W. Corner of the Diminished Umatilla Indian Reservation, I set a witness corner monument. The witness corner monument is a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe. The top of the monument is about 6" below the top of the corner stone and about 21" below the top of the ground. The monument is about 12" west of the east edge of a wheat field. Referenced the witness corner as follows. From the witness corner monument:

A 1 1/2" yellow plastic cap marked "W.R. Wells PLS 1106", set on a 2 1/2" by 30" iron rod bears S59°E 20.92'. Set steel fence post near reference monument and attached witness corner and bearing object sign.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears N49 1/2°E 24.12'. Set steel fence post near reference monument and attached witness corner and bearing object sign.

The aluminum cap on the reference monument is marked as follows:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)