

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 33E., W.M.


Corner Code No. J-1

Note: Monument marked as shown below

History of original corner establishment:

This corner had been established and re-established a number of times prior to 1917.

In 1917, L.E. Wilkes, under Group 29 Instructions, made a resurvey of the diminished Umatilla Indian Reservation boundary, re-established the corner and monumented it with a iron post, 3" long and 2" in diameter.



Corner No.
Compass Declination 18.0

Description of corner evidence found:

Wilkes bent 1917 monument, a 2 1/2" brass cap on a 2" galv. iron pipe, the top of which was 18" below ground.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the base of the recovered Wilkes monument, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized pipe, with the top of the cap 1' below existing ground.

Set steel fence post 1' North of corner and attached witness corner sign.

Referenced the remonumented corner as follows:

A brass washer stamped "PLS 1106" in the East side of a power pole 6" above ground, bears N 7° W 35.92'. Attached bearing object sign to the pole. Top of the most Easterly guy wire extending from the pole mentioned above bears N 39° E 67.3'. (Measure to where the guyline enters the ground). The Northerly edge of the steel post for County Road "Milepost 1" bears S 18° E 77.4'. (Measure to where post enters the ground). Attached bearing object sign. The Southeast corner of Section 12 bears S 00° 06' 35" E 258.44'.

Buried Wilkes corner monument alongside of new monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey Dept. County of Umatilla
State of OR, I hereby certify that the within instrument was filed in this office
for record on the 19th day of July, 1990
David H. Hammond by Kathleen K. Amberg
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Survey Dept
Date 7-90
Initials KA
No 90-50-C
☆ GPO: 1989-692-049