

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/06/12

CORNER DESIGNATION: L-1, The West Quarter Corner of Section 18, Township 2 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner re-established by L. E. Wilkes, under special instructions dated February 20, 1917, under Group No. 29. Notes state: The 1/4 corner of section 18 falls in the road. 1.00 chain East of the corner point, on right bank of Tutuilla Creek (Patawa Creek) Set an iron post, 3 ft. long, 2 ins. In diam., 24 ins. In the ground, for the witness corner to the 1/4 corner of section 18.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2N
R32E|R33E
| 1/4 S18
2012
PLS 54657

MONUMENT SET: Corner point was calculated by single proportion measure along the Range line holding L.E. Wilkes record distance from the 1/4 corner of section 13. At calculated corner point, set a 2 3/8" brass cap on a 1 1/4"x 30" galvanized iron pipe with cap 2" above ground level in 4 foot diameter mound of stone. marked as shown in "Monument Marking Detail".

From which:

A 5/8"x24" iron rebar with a 1 1/4" purple plastic cap marked "Wells Surveying 54657 PLS" bears North 08°34'44" East, 298.35 feet.

A 3/4" brass washer stamped "PLS 1106" 2.0 feet above ground level in a 10"x10" wood guard rail post bears North 83° East, 50.9 feet.

A 3/4" brass washer stamped "PLS 1106" 1.0 foot above ground level in a 12" wood fence corner post bears South 23° West, 23.0 feet.

A 2" aluminum cap 4" below gravel road surface marking the East 1/4 corner of Section 13, T2N, R32E, bears South 00°01'23" West along the Range line, a distance of 181.86 feet.

Bearing object signs are attached to the wood posts near the two brass washers. Set a steel fence post with a witness post sign attached 4 feet North of the corner monument.

LOCATION AND COMMENTS: Corner falls at the top of rip rap fill on the Westerly bank approximately 30 feet from Patawa creek in a barnyard area. The center of the Easterly side of the barn is approximately 75 feet Westerly. See Partition Plat No. 2012-07 for more information on this corner.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Dean Roy

/2N33L1

RECEIVED BY
Umatilla County Surveyor
Date: 5/12/2012
Rec'd By: Janey Nabert
No.: 12-065-B



RENEWS: 6-30-12