

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/05/97

CORNER DESIGNATION: L-9, The West Quarter Corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.: Found 1/2" iron pin for corner point and accepted it. No record for pin, see Survey No. 92-16-B.

MONUMENT MARKING DETAIL:

T2N R33E
1/4
S17 | S16
1997
PLS 1106

MONUMENT SET: At position of found 1/2" iron pin, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 72° E, 5.39 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 31° E, 9.25 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 28° W, 9.15 feet.

A 4" iron pipe bears N 01° W, 3.8 feet. This is a field line marker pipe about 4 feet above the ground.

All rebar have bearing object signs and fence posts nearby with survey marker signs attached.

LOCATION AND COMMENTS: Corner falls in edge of farmed field.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: John Linder, LSIT
Jason Wells



renews 6-30-98

RECEIVED BY
Umatilla County Surveyor
Date: 11-97
Rec'd By: KK
No. 97-222-C