

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/09/03

CORNER DESIGNATION: N-5, the Northeast Corner of Section 19, T2N, R33E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was most recently established by Currin and Noland under Special Contract dated May 4, 1887. Currin and Noland notes call for a charred stake, with pits and mound and a scribed stake. Based on testimony by Dave Umbarger, this corner was likely recovered or re-established by C.E. Redfield, U.S. Indian Service Survey around 1918, but I find no Redfield notes for recovery or re-establishment. This corner was re-established immediately North of an East-West fence line, 16 1/2 feet West of a fence corner with fences extending East-West and South, per testimony by Dave Umbarger, in 1992 and 2003, who observed the corner monument prior to it's removal. Steve Umabarger, also indicates he saw a brass cap monument in the vicinity as a boy. Also see Survey No. 92-016-B, for a tie to the corner position.

MONUMENT AND ACCESSORIES FOUND: None. Corner point falls just North of a East-West fence line.

MONUMENT MARKING DETAIL:

T2N R33E
S18 | S17

S19 | S20
2003
PLS 1106

MONUMENT SET:

Re-established corner position per testimony by Dave Umbarger. The re-established corner position fits within 1.8 feet in departure, when compared to the Northerly extension of a line between the recovered Southeast Corner of Section 19 and the recovered South 1 /16th Corner of Section 19. A the re-established corner position, set a 2 1/2" brass cap on 1 1/4" by 30" galv. iron pipe 24" in the ground. Cap is marked as shown on "Monument Marking Detail".

New Accessories:

A irrigation riser head near the end of a 6" irrigation pipe bears N 88°E 13.6'.

A irrigation riser on same irrigation pipe bears S 89°E., 112.7'

A 5/8" by 24" rebar, with yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears S 37 1/2° E., 26.8'. Wired "bearing object" sign to the rebar. This rebar is in a North-South fence line.

A 5/8" by 24" rebar, with yellow plastic cap marked "OR PLS 1106 WA PLS 17372" bears West., 28.3'. Wired "bearing object" sign to the rebar. This rebar is in a East-West fence line.

Nailed "Witness" sign to a wood fence post 2 ft. West of corner.

LOCATION AND COMMENTS:

Corner falls just North of a East-West fence line, 16 1/2' West of a fence line extending South.

STATE PLANE COORDINATES, OREGON NORTH, NAD 83(91), International Feet:

N = 726575.55
E = 8655838.04

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
2N33N5

