

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/05/97

CORNER DESIGNATION: N-9, The Northeast Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner position was calculated per Survey No. 92-16-B.

MONUMENT MARKING DETAIL:

T2N R33E
S17 | S16
S20 | S21
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe approximately 6" below surface of gravel road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 15° E, 33.8 feet, cap buried 6" below road surface.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 37° E, 18.3 feet, cap buried 6" below road surface.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 46° W, 19.78 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 69° W, 12.94 feet.

The iron pin bearing objects in the Southwest and Northwest quadrants have steel fence posts set near iron pins with survey marker signs attached.

LOCATION AND COMMENTS: Corner is located in Billy Road, County Road No. 1043.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: John Linder, LSIT
Jason Wells

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RENEWS 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 11-97

Rec'd By KK

No. 97-222-C