


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index:

Intersection of NE 41st Street and Riverside AVE. in Pendleton Oregon. Corner originally set by F.B. Hayes in the Plat of the Crispin Riverside Tracts. His record reads: Set a 6"x 6"x 24" concrete plug with a copper pin 6" below the surface of the ground.



Description of corner evidence found:

A 24" diameter concrete ball with a 2 1/2" brass disc was lying in the street having been removed by construction equipment. Mr. Ralph Thompson testified that he was the one who set this cap. The original Crispin Riverside monument was still in place. The copper pin was a copper wood screw.

Description of monument and accessories I established to perpetuate the original location of this corner:

As the original Crispin Riverside monument had not been disturbed by the construction equipment, PK nails were driven in the pavement to use as straddles to replace the monument with. After the construction was complete, a 18" x 18" hole was excavated at the point for the monument. A 5/8" x 18" smooth iron pin was driven in the bottom of the hole to provide ferrous material for a pin locator to pick up. This pin was not at the exact corner point. The remainder of the hole was filled with concrete and a 2 1/2" brass disk was set at the exact monument location. An aluminum water valve jacket was used for a monument case. The brass disk was stamped as in the diagram above.

This work was done June 21, 1996 and witnessed by Stephen Haddock.

Office of Co. Surveyor County of Umatilla  
State of OR, I hereby certify that the within instrument was filed  
in this office for record on the 27<sup>th</sup> day of June, 1996.  
( COUNTY OFFICIAL ) by ( DEPUTY )

REGISTERED PROFESSIONAL LAND SURVEYOR

David L. Haddock

OREGON JULY 12, 1968 DAVID L. HADDOCK 852

RECEIVED BY  
Umatilla County Surveyor  
Date 6-76  
Rec'd By KK  
No. 96-108-R