

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/22/94

CORNER DESIGNATION: X-25. East 1/4 corner Section 36, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by L.E. Wilkes, GLO Cadastral Surveyor, in 1917. Wilkes set an iron post, 3 ft. long, 2 ins. diam., with brass cap, 24 ins. in the ground for a witness corner to the 1/4 corner. Witness corner was located 45 1/2 lks. West of the true corner point.

MONUMENT AND ACCESSORIES FOUND: Found Wilkes witness corner monument lying on ground, destroyed by power pole installation. NOTE: Prior to power pole installation about 5 years ago, I had seen this witness corner monument in place, just South of the fence corner, about where the power pole is now located.

MONUMENT MARKING DETAIL:

T2N
R32E R33E
1/4
|
S36 . S31
|
1994
PLS 1106

MONUMENT SET: Re-established corner position on line between the North 1/16th corner of Section 31 and the Southeast corner of Section 36, holding existing power pole for latitude. At the re-established corner position, set a 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe, 43" in ground.

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 64° E-25.0 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 50° E-30.9 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 29 1/2° W-41.9 feet.
Power pole No. 369561 with a brass washer stamped "PLS 1106", nailed 0.3 feet above ground, bears N 88° W-17.3 feet.
Attached bearing object signs to iron pins and above brass washer on pole. Set steel fence post guards near iron pins with witness signs attached. Attached witness sign to power pole.

LOCATION AND COMMENTS: Corner is located in the center of the West lane of Powerline Road.

COMPASS DECLINATION: 18° East
FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

RECEIVED
JUL 2, 1994
WILLIAM R. WELLS
1105