


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Charles L. Campbell under GLO contract number 733, dated March 22, 1901. Surveyor General record states:

Set ironstone 15x10x4 ins, 10 ins. in the ground for cor. of secs. 1,2,11 and 12, marked with 1 notch on E. and 5 notches on S. edges, from which
A Fir, 48 ins diam bears N42°E, 43 lks dist marked T2N R37E S1 BT
A Fir, 24 ins diam bears S40°E, 43 lks dist marked T2N R37E S12 BT
A Tamarack, 36 ins diam bears S20°W, 42 lks dist marked T2N R37E S11 BT
A Fir, 30 ins diam bears N74°W, 84 lks dist marked T2N R37E S2 BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument.

Found a 25 inch diameter fir stump S40°E, 28.4 feet with blaze evident.

Found a 35 inch diameter Douglas Fir snag S20°W, 27.7 feet with scribes visible.

Found no evidence of the original Northeast and Northwest bearing trees.

Description of monument and accessories established to perpetuate the

original location of this corner: At record bearing and distance from the found original bearing trees, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New Bearing Trees and Bearing Objects;

A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N35°E, 4.85 feet
A 28 inch diameter Western Larch bears S14°E, 147.1 feet marked T2N R37E S12 BT
A 18 inch diameter Spruce bears S3°W, 143.65 feet marked T2N R37E S11 BT
A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N77°W, 4.98 feet

Painted a 6 inch red band around all bearing trees and attached Bearing Tree and Land Survey Monument signs.

Set a steel fencepost approximately 5 feet South with Land Survey Monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 13, 1991.

Witness: Jeff Petersen



I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-9-92
Rec'd By KK
No. 92-119-R