


Index
 File No. **T. 2 N. R. 37 E.**
 Merid. **WILLAMETTE**

CORNER RECORD (SEARCH)
 (Ref. FSM 7151.4)

Tract or Survey No. **NF UMATILLA**
 County **UMATILLA**
 State **OREGON**

Cor. No. **AP-950**

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:
 Filed At.:
 Object Ident.:
 Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located on the south bank of the drainage which drains Whitman spring at a point where the crest of a ridge intersects the natural flow line.

PLANE COORDINATE POSITION

State: OREGON Zone: NORTH
 X: 2,599,772.94'
 Y: 742,586.89'
 Datum: NAD1927

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
11/1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 12" in the ground surrounded by a rock mound 1 1/2' in diameter by 1' high, mkd. "NF UMATILLA WILDERNESS AP-950 RLS 2308 1993"

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

20" Douglas Fir, N. 39° W., 17.0 ft., mkd. "WB/950""BT".
11" Douglas Fir, S. 67° W., 69.7 ft., mkd. "WB/950""BT".

The BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich

Title Land Surveyor

Date 11/1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? NO

Filed At

Date

REMARKS

Index File No.

T.

2 N.

R.

37 E.

M.

W.M.

Tract or Survey No.

NF UMATILLA

Cor.

AP-950