

Index

File No. **C.83-17**

T. 2 N. R. 37 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. WALLA-WALLA

N.F. UMATILLA

County UMATILLA

State OREGON


Tract or

Survey No. **NF UMATILLA**

Cor.

No. **AP-932**

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,598,865.40'

Y: 742,155.45'

Datum: NAD1927

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the intersection of Buck Mtn. trail (old rd 3150) with the section line of sections 2 & 3, go South following the section line and the posted wilderness boundary approx. 1500 feet to the corner, which is located on the south bank of the creek which drains Whitman Spring.

Signature

D. Gaylord

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06/1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 12" in the ground surrounded by a stone mound 1 1/2' in diameter by 1' high, mkd. "NF UMATILLA WILDERNESS AP-932 PLS 1636 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

13" Douglas Fir, S. 35 1/2° W., 32.5 ft., mkd. "WB/932""BT".

26" Douglas Fir, N. 87° W., 32.7 ft., mkd. "WB/932""BT".

The BT's are double blazed and have a 3/4" brass washer mkd. "PLS 1636" nailed next to the "BT" scribing on the lower blaze.

Work Done By **D. Gaylord**

Title **Land Surveyor**

Date **06/1993**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

C.83-17

T.

2 N.

R.

37 E.

M.

W.M.

Tract or Survey No.

NF UMATILLA

Cor.

AP-932