


LAND CORNER RECORD

1. T. 2N R. 37E No. 35 Cor. NE Mer. W State Oregon N. F. # 11 Umatilla Dist. # 3 Pendleton

2. Corner Status



3. Original Description _____ Vol. _____ Page _____ Where Recorded County Court Hse.

4. Description of Corners: Basalt stone, 15x10x6 in. -- in ground.
Bearing Trees: Marked with 1 notch on S. and E. edges.
Spruce, 18 in. diam. bears N55°E 35 Lks. marked T2N, R37E; S 25 BT.
Tamarack, 36 in. diam. bears S10°E 82 Lks. marked T2N, R37E; S 36 BT.
Fir, 18 in. diam. bears S52°W 106 Lks. marked T2N, R37E; S 35 BT.

~~#####~~ Bearing Trees cont'd:
Fir, 10 in. diam. bears N70°W 55 Lks. marked T2N, R37E; S 26 BT.

7. Photo Identification
Photo No. DVD-6M-80
Ident. By: _____

8. Plane Coordinate Position Data
State _____ Zone _____
X _____
Y _____
Estab. By _____
Field Book No. _____
Where Filed _____

9. Evaluation
Authentic _____
Needs Verif. Monument No
Re-estab. _____ Survey _____
Land Status _____

5. Investigation notes: All four Bearing Trees for this corner have been found. As the corner is in a clear-cut area, the timber has been logged off on all sides of the corner and a small stand left uncut around the corner to protect it. The stone has not been located.

6. Signed A. Arthur Title Forester Date 2-23-61

PERPETUATION RECORD

10. Monument:

11. Accessories

Field Book _____ Page _____

12. Set By _____ Title _____

13. Recorded By _____ Volume _____ Page _____
(Agency)

License _____ Agency _____ Date _____

(Date) (City) (County) (State)

14. Remarks:

V-21