

USDA-FOREST SERVICE

Index

File No. A-2

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

T 1N R. 38E

R.D.

Walla Walla

County

Tract or Survey No. _____

Union

Cor. No. _____

Merid. Willamette


N.F.

Umatilla

State

Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. F16616160 1577-123

Filed At. Umatilla Nat. F.

Object Ident. Direct

Ident. By G. Landlitz

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Gary A. Hough
Signature

Title
Land Surveyor

Division
PLS 1099

Headquarters _____

Date

10/6/80

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Corner set from survey by single proportionate measurement. R T2N
 At the corner point, we set a 2"x30" Galvanized Iron Pipe, 38 S31
 20" in the ground to bedrock, and in a mound, stone 4' dia. to top of E S6 W 1/16
 pipe, with a brass cap attached, stamped: T1N

PLS 1099
 1980

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which we mark new BTs: A 16" Douglas Fir, scribed "W 1/16 S6 BT" on a double blaze bears S30⁰ E 66.3 ft. And a 12" Larch, scribed "W 1/16 S31 BT" on a double blaze bears N50⁰ E 75.2 ft. Attached brass washer, marked "LS 1099" to lower blaze of each BT. Placed steel fence posts 5 ft. S and E of monument with signs 54-2 and 54-9 attached to southerly post and sign 54-2 only on easterly post. Attached signs and painted BTs per Standard Specifications for Cadastral Survey, U.S.F.S., Region 6 Oct., 1979.

Work Done By Gary Langlitz Title Land Surveyor Date 10/6/80 State Registration No. PLS 1099
 or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor Date Dec., 1980

REMARKS

Compass Declination: 18⁰ East

Witness: John Curtiss