

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 21  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin, deputy, (compassman) on October 24, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 16" x 9" x 6", on west side of hill for section corner to sections 1, 2, 35 and 36, T. 1 & 2 S., R. 30 E.

T1S R30E  
S35/S36  
S2/S1  
T2S  
PLS 1636  
2002

**Original corner evidence recovered:**

Found the original corner stone loosely set in a mound of stones. The corner stone is 16" x 11" x 6" and is plainly marked with one notch on one edge.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 11" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone alongside the north side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 36", attached at ground level, bears N45° 30' E, 114.0 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears S29° 30' E, 130.5 feet.

A 5/8" x 18" iron rod set 18" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears S45° W, 151.8 feet.

A 5/8" x 18" iron rod set 18" into the ground with a 3/4" brass washer, marked "PLS 1636 35", attached at ground level, bears N66° 30' W, 70.2 feet.

I nail a "witness post" sign to a wooden fence post 15.5 feet south of the corner.

I hereby certify this corner point was perpetuated as hereon described on March 13, 2002.

Magnetic declination set in compass: 18° E.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**  
*Dennis L. Gaylord*  
**OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636**

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

**RECEIVED BY**  
**Umatilla County Surveyor**  
Date 6-02  
Rec'd By KR  
No. 02-142-R