


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 5, 1878, under GLO contract No. 293, as follows:

Set a stone, 16" x 8" x 6", for 1/4 section corner.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 17" x 8" x 8" and is plainly marked "1/4".

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 16" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone alongside the east side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N29° 30' E, 147.7 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S58° E, 115.3 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S24° W, 148.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N62° W, 79.0 feet.

I nail a "witness post" sign to a wooden fence post at the corner.

I hereby certify this corner point was perpetuated as hereon described on January 30, 2002.

Magnetic declination set in compass: 16° E.



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: _____

RECEIVED BY
Umatilla County Surveyor
Date 2-02
Rec'd by KR
No. 02-30-R