


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 11, 1878, under GLO contract No. 293, as follows:

Set a stone, 18" x 12" x 4", for 1/4 section corner.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 19" x 11" x 4" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N48° E, 71.3 feet.

A 5/8" x 18" iron rod set 12" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S74° E, 88.6 feet. I build a small mound of stones around this reference monument.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S47° W, 67.4 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N52° W, 65.6 feet.

I nail a "witness post" sign to a wooden fence post 0.5 foot north of the corner.

I hereby certify this corner point was perpetuated as hereon described on February 25, 2003.

Magnetic declination set in compass: 16° E.

NAD '83 UTM Zone 11 position: 5032034N 333764E (plus or minus two meters).

A professional seal for Dennis L. Gaylord, a Registered Professional Land Surveyor in Oregon. The seal includes his signature and the text: REGISTERED PROFESSIONAL LAND SURVEYOR, OREGON, JULY 14, 1878, DENNIS L. GAYLORD, 1636.

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 5-03
Rec'd By JK
No. 03-71-R