


CERTIFIED RECORD OF LAND CORNER MONUMENTATION.

E - 25
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 7, 1871, under GLO contract No. 154, as follows:

Set a stone, 26" x 8" x 6", for corner to sections 1, 12, 6 and 7.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The original corner stone is 26" x 7" x 6" and is plainly marked with one notch on a (north) edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 23" into the ground. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S6", attached at ground level, bears N55° 30' E, 144.8 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S7", attached at ground level, bears S52° 30' E, 147.4 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears S42° W, 146.4 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears N35° W, 104.5 feet.
- This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on January 28, 2005. Magnetic declination set in compass: 16° E.
NAD '83 UTM Zone 11 position: 5031264N, 332091E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-05
Rec'd By KK
No. 05-020-R
E-1