

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 21
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 3, 1878, under GLO contract No. 293, as follows:

Set a stone, 16" x 10" x 8", on southwest rocky hillside for corner to sections 1, 2, 11 and 12. Cannot dig pits. I build a mound of stone around stake in lieu of pits.

T2S R30E
S2|S1
S11| S12
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones, but tipped to the east. The corner stone is 18" x 8" x 6", and is plainly marked with one notch on the north and one notch on the east edges. The post of record is gone.

Monument and accessories established to perpetuate the original position of this corner:

At the exact point occupied by the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 12" into the ground to bedrock. I bury the corner stone along the east side of the pipe and build a large mound of stones around the pipe. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears N14° 30'E, 146.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S12", attached at ground level, bears S48°E, 117.5 feet.

A spring on the hillside bears S37°E about 300 feet.

A 5/8" x 18" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 S11", attached at ground level, bears S50° 30' W, 66.3 feet.

A developed spring, west of a creek about 25 feet, bears N77° W, about 400 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears N41° W, 134.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 31, 2002. Magnetic declination set in compass: 18°E.


**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-02
Rec'd By KK
No. 02-166-A