


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 9, 1878, under GLO contract No. 293, as follows:

Set a stone, 17" x 10" x 7", for corner to sections 4, 5, 8 and 9. Dug pits and drove a willow stake as per instructions.



Near here, in July, 1878, Mr. Nelson and Mr. Jewell were shot and killed by Indians.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The original corner stone is 17" x 8" x 7" and is plainly marked with four notches on the east edge and one notch on the north edge. The stake and pits of record are gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 S4", attached at ground level, bears N34° 30' E, 103.6 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S9", attached at ground level, bears S33° 30' E, 132.4 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S8", attached at ground level, bears S50° 30' W, 168.8 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S5", attached at ground level, bears N42° 30' W, 140.6 feet.
- I nail a "Witness Post" sign to a wood fence corner post which bears N60° E, 1.0 foot.
Barbed wire fences project north and east from the corner.

I hereby certify the above corner point was perpetuated as hereon described on February 11, 2004. Magnetic declination set in compass: 23° E. (Possible local attraction due to fence wires, however, corners to north and east are visible from here) NAD '83 UTM Zone 11 position: 5031180N, 335387E (plus or minus two meters).

REGISTERED PROFESSIONAL LAND SURVEYOR
Dennis L. Gaylord
OREGON JULY 14, 1978 DENNIS L. GAYLORD 1636

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-04
Rec'd By KK
No. 04-37-R