

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G - 13
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 6, 1878, under GLO contract No. 293, as follows:

Set stone, 17" x 10" x 8", on the south side of a ravine for the 1/4 section corner.

T2S R30E
1/4
S9|S10
PLS 1636
2000

Original corner evidence recovered:

Found the original corner stone solidly set with one small stone alongside the south and one small stone alongside the north of the corner stone, and a large, rusty horseshoe alongside the west side of the corner stone. The corner stone is 17" x 11" x 7" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the horseshoe around the pipe, 25" below the ground surface, and bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N86° 30'E, 67.3 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S21° 30'E, 57.0 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S33° 30'W, 117.6 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N76° 30'W, 45.8 feet.

All four of the references are south of the bottom of Webb Slough, which is subject to flash flooding.

A 5 foot steel fence post with a "Witness Post" sign attached bears south, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 23, 2000. Magnetic declination set in compass: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylor
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-2000
Rec'd By JK
No. 00-158-R