

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 4, 1878, under GLO contract No. 293, as follows:

Set stone, 14" x 12" x 6", on south side of ravine for 1/4 section corner.

T2S R30E
1/4
S10|S11
PLS 1636
2000

Original corner evidence recovered:

Found the original corner stone solidly set with two stones alongside. The corner stone is 16" x 11" x 8", and is marked "1/4" on the west face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N68°E, 119.0 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S41°E, 67.9 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S59°W, 66.6 Feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N25°W, 131.4 feet.

The two references to the north are north of, and across a ravine from the corner.

A 5 foot steel fence post with a "Witness Post" sign attached bears South, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 23, 2000. Magnetic declination set in compass: 18°E.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
Dennis L. Gaylord
**OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636**

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-2000
XR
00-139-R