

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 11, 1878, under GLO contract No. 293, as follows:

Set a stone, 13" x 10" x 8, for the 1/4 section corner.

T2S R30E
1/4
S7|S8
PLS 1636
2004

Original corner evidence recovered:

Found the original corner stone solidly set 10" in the ground on the north edge of a mound of stones. The corner stone is 19" x 12" x 9" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 14" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N45° E, 146.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S40° E, 92.0 feet.
- A 5/8" x 24" iron rod set 22" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S66° 30' W, 110.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N45° 30' W, 71.0 feet.
- A barbed wire fence projecting N70° W - S70° E, bears South, 95.0 feet.
- I nail a "Witness Post" sign to a wood fence post which bears S16° E, 110 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 9, 2004. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5030418N, 333745E (plus or minus two meters).


REGISTERED PROFESSIONAL LAND SURVEYOR
 OREGON
 JULY 14, 1978
DENNIS L. GAYLORD
 1636

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 2-04
 Rec'd By KK
 No. 04-58-R