

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 15
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 6, 1878, under GLO contract No. 293, as follows:

Set stone, 14" x 12" x 7", for 1/4 section corner.

T2S R30E
1/4 S10
S15
PLS 1636
2000

Original corner evidence recovered:

Found the original corner stone solidly set with one small stone alongside the east and one small stone alongside the west of the corner stone. The corner stone is 14" x 13" x 6", and is marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 22" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N44° 45'E, 121.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S60° 30'E, 128.8 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S38°W, 85.6 Feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N21° 30'W, 109.4 feet.

A 5 foot steel fence post with a "Witness Post" sign attached bears West, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 23, 2000. Magnetic declination set in compass: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY

Umatilla County Surveyor
Date: 6-2000
KR
00-140R