

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 21
DIAGRAM

History of original corner establishment:

The original corner was established on September 3, 1878, by George S. Pershin under GLO contract No. 293, as follows:

Set a stone, 17" x 10" x 6", for the corner to sections 11, 12, 13 and 14. Dug pits and drove pine stake per instructions.

T2S R30E
S11|S12
S14|S13
PLS 1636
2000

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 17" x 13" x 11" and is marked with 2 notches on one edge and one notch on the opposite edge. The stake and pits set in the original survey are gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 14" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I partially bury the corner stone to the north and build a mound of stones around the corner stone and pipe, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N53° 30'E, 128.7 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S44° 30'E, 148.0 feet.
- A 3/4" x 18" iron rod set 18" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S48° 30'W, 162.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N50° 30'W, 119.9 feet.
- A 5 foot steel fence post with a "Witness Post" sign attached bears south, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 13, 2000. Magnetic declination set in compass: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 11, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-2000
Rec'd by KR
No. 00-127-R