

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 23  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 3, 1878, under GLO contract No. 293, as follows:

Set a stone, 20" x 10" x 6", for the 1/4 section corner.

T2S R30E  
1/4 S12  
S13  
PLS 1636  
2000

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 22" x 12" x 7" and is plainly marked "1/4".

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 20" into the ground to bed rock. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone to the northwest of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N60°E, 63.8 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S87°E, 52.2 feet,

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S49° 30'W, 95.3 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N89°W, 68.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 20, 2000. Magnetic declination set in compass: 18°E.



Renews June 30, 2001

Recorded at the office of County surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
DATE 6-20-00  
BY XR  
00-141-R