


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

N - 25  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on September 7, 1871, under GLO contract No. 154, as follows:

Set a stone, 24" x 8" x 5", on southwest hillside for corner to sections 13, 24, 18 and 19.



**Original corner evidence recovered:**

Found the original corner stone solidly set on the east edge of a mound of stones. The original corner stone is 23" x 10" x 6" and is plainly marked with three notches on the north edge.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 20" into the ground. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N40° E, 83.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S43° 30' E, 86.0 feet.

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S29° 30' W, 58.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N23° W, 72.0 feet.

A farm road projecting northeast and southwest bears East, 32.0 feet.  
This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on January 25, 2005. Magnetic declination set in compass: 16° E.  
NAD '83 UTM Zone 11 position: 5028035N, 332015E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 2-05  
Rec'd by KK  
No. 05-022-R  
N-1