

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 13  
DIAGRAM

T2S R30E  
S16|S15  
S21|S22  
PLS 1636  
2002

**History of original corner establishment:**

The original corner was established by George S. Pershin on September 6, 1878, under GLO contract No. 293, as follows:

Set a stone, 16" x 10" x 6", for corner to sections 15, 16, 21 and 22. Dug pits and drove a alder stake as per instructions

**Original corner evidence recovered:**

Found the original corner stone loosely set in a mound of stones. The corner stone is 14" x 8" x 7" and is plainly marked with three notches on one (east) edge and three notches on another (north) edge. The stake and pits of record are gone.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 8" into the ground to bed rock. A 2 1/2" brass cap attached to the top of the iron pipe is marked as shown in the diagram above. I place the corner stone horizontally along the north side of the pipe and build a mound of stones around the corner stone and pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 15", attached at ground level, bears N56° E, 107.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 22", attached at ground level, bears S49° 30' E, 149.6 feet.

A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 21", attached at ground level, bears S58° 30' W, 130.1 feet.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 16", attached at ground level, bears N38° 45' W, 114.5 feet.

I nail a "Witness Post" sign to a wood post 12.5 feet west of the corner.

I hereby certify the above corner point was perpetuated as hereon described on July 31, 2002. Magnetic declination set in compass: 18° E.

  
**REGISTERED PROFESSIONAL LAND SURVEYOR**  
OREGON  
JULY 14, 1974  
**DENNIS L. GAYLORD**  
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 9-02  
Rec'd By KF  
No. 02-216-R