

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 15
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 6, 1878, under GLO contract No. 293, as follows:

Set a stone, 18" x 13" x 7", for the 1/4 section corner.

T2S R30E
1/4 S15
S22
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone solidly set but tipped down hill to the east. The corner stone is 18" x 16" x 7" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the top of the iron pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N38° E, 108.8 feet.


A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S26° E, 134.4 feet,

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S55° W, 68.4 feet.


A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N36° W, 135.5 feet.

I nail a "Witness Post" sign to a steel fence post four feet west of the corner.

I hereby certify the above corner point was perpetuated as hereon described on July 31, 2002. Magnetic declination set in compass: 18° E.



Dennis L. Gaylord



Renews June 30, 2003

Recorded at the office of County surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 9-02
Rec'd By JK
No. 02-216-R